

Programmed Hoist Passivation Systems





- 100% Stainless Steel construction for tanks, frame, hoist and exhaust
- Polished Stainless Steel exterior surfaces



- Unitized tank construction prevents acid spills between tanks
- Rear lip exhaust vent



- Hoist lines are completely assembled for shipment in one piece
- Base and frame are 100% Stainless Steel construction
- All plumbing is complete to a single point for water header, tank fills, level controls, air, filters, chemical feed systems, and tank drains
- · Hoist is mounted, wired and test run prior to shipment
- Electrical connections are complete to all components and all wiring is complete to a central control panel



- Dryers use 100% recirculation for energy efficiency
- All ducting is Stainless Steel
- Parts are transported through dryer automatically on Stainless conveyors





 Air knives are used for spot free drying of critical components prior to the dryer

Distributed By:



www.manleyequipment.com Contact info: +1 972-839-6117 info@manleyequipment.com